

Maintaining The MWA's Electronic Systems

December 2020

Presented by Phillip Giersch, Curtin University/MWA

WWA Electronic Equipment

- Antennas
 - Low Noise Amplifiers
- Beamformers
 - Delay Line Boards
 - BF Docs
 - CPLD Boards
- Receivers
 - Receiver Doc's
 - Coaxial and fibre Cabling
- BFIF's
 - Solar charging Circuits





And Much More

Beamformer Upgrade Project 2020-2021

- Refurbish and Upgrade 256 Beamformers
- Objective
 - Extend the lifespan of the fielded beamformers
 - Replace components that have now been made "end of life" by their manufacturer.
 - Bringing the reliability of all beamformers of different ages up to an equivalent service state

• Status

- 90 Beamformers Currently
 Processed
- Expected completion December 2021



Beamformers Removal and Installation

• Tasks

• Power down the tile

- Transport all Tools and Spare beamformer to Tile
- Swap The Following between Beamformers
 - 32 SMA Cable
 - 2 F-type cables
 - GND Cables
 - Feet
 - Rain shield
- Check All SMA Cables
- Repair any faults with tile
- Box up the Beamformer and ship To Perth

Beamformer Contents

- Delay line Board x2
- Beamformer Doc
- CPLD Board
- 32 SMA Lock washers
- 32 SMA Nuts
- 32 Nylon Washers
- 4xShort, 8xLong Standoffs
- 40 pin Ribbon cable x2
- Dual output
- LED Status Harness
- CPLD To DOC Ribbon Cable
- Power Ribbon Cable



Delay Line Board Upgraded Parts

- U230 Output Amplifier upgraded to QPB7420
- Daughter board fitted to U230 Output Amplifier
- Input amplifiers upgraded to QPA4563A
- Post Summing Amplifier U229 replaced with QPA4263A





U230 output amplifier test points



Input amplifier stage test points





- Input SMA voltage tests
- Original Setup



2021 Version



Voltage Tests on summing Amplifier



Beamformer Test Setup



Vector Network Analyser



Spectrum Analyser

Good Results From Our Test Setup

Spectrum Analyser Output



Vector Network Analyser Output



Image: credit MWA

See: VNA_output_slide10.mp4



- 48 Hour Test Cycle
- Minimum 50,000 successful pointing sent and received
- Fully loaded down with 50 ohm terminators to simulate an LNA
- Current draw measured to confirm all
- Once Soak test Completed all input Voltages are checked & all VNA and Spectrum Analyser checks repeated
- The Beamformer can then have its final screws placed in paperwork completed Boxed up ready for delivery to site

• Rev 1



• Rev2





 Can Be Caused by cracked Capacitors failed inductors Leaking RF switches damaged summing transformers

Severe example with Distortion in Both Gain And Delay on a single channel



Good Signal not under load



Beamformer RF Comb



Rx: 10 Slot: 1 Polarization: X Recorded at 2020-06-29 0 A Rx: 10 Slot: 1 Polarization: Y Recorded at 2020-06-29 0 A Rx: 10 Slot: 1 Polarization: Y Recorded at 2020-06-29 0 A Rx: 10 Slot: 1 Polarization: Y Recorded at 2020-06-29 0 A Rx: 10 Slot: 1 Polarization: Y Recorded at 2020-06-29 0 A Rx: 10 Slot: 1 Polarization: Y Recorded at 2020-06-29 0 A Rx: 10 Slot: 1 Polarization: Y Recorded at 2020-06-29 0 A Rx: 10 Slot: 1 Polarization: Y Recorded at 2020-06-29 0 A Rx: 10 Slot: 1 Polarization: Y Recorded at 2020-06-29 0 A Rx: 10 Slot: 1 Polarization: Y Rx: 1







Micro fractures in daughter board capacitor

• Causes

- Thin PCB substrate
- Depanelizing Process
- Capacitor position on PCB
- Exacerbated by
 - Temperature shifts.
 - Movement.
 - Rework.
 - Handling.



Cracking Problems in Low-Voltage Chip Ceramic Capacitors

Teverovsky, Alexander (*Jacobs Engineering Group, Inc. Edwards AFB, CA, United States*) https://ntrs.nasa.gov/citations/20190001592



See: micro_fractures_slide14.mp4

Daughter board





New Flex term capacitors fitted to all existing and future daughter boards

Image: credit MWA

Upgraded version





- -60db Spike generated between 0 and 100MHz
- Only observed when the beamformer enclosure is closed



Spike Shown on Spectrum analyser

Good Signal not under load







Questions

Presented by Phillip Giersch, Curtin University/MWA